195' PRODUCTION BARGE



PRODUCT DESCRIPTION

195' PRODUCTION BARG

195' x 35' x 12'
Bulkheads 5/16"
10-Deck longitudinal angles 5” x 3” x 5/16”.
10-Bottom longitudinal angles 6” x 3.5” x5/16”.
4-Side longitudinal angles 5” x 3.5” x 5/16”
10-Aft bulkhead vertical angles 5” x3.5” x 5/16”
8-Bulkhead gussets 16” x 5/16” x 16” (forward and aft)
10-Bulkhead gussets upper 12” x 3/8” x 1’ (forward and aft)
10-Bulkhead gussets lower 12” x 3/8” x 1’ (forward and aft)
7-Truss frames were construction out of the following:
NOTE: Truss frames are set 5’ aft the forward bulkhead and set 5’ apart thereafter.
Overhead transverse deck girder 8” @ 11.5 lbs. channel
Lower transverse deck girder 12” @ 20.7 lbs. channel
Outboard girders 10” 15.3lb channel
Inboard girders 5” x 3” x 5/16”
3-Vertical stiffeners 5” x 5” x 5/16” angle
4-Diagonal stiffeners 3” x 3” x 5/16” angle
1-Longitudinal diagonal angle 6”x 5/16” x 6” angles

Categories: Barges
Additional Information Approximately $500K of work done in 2024.







COMMERCIAL MARINE PRO